ADDENDUM 1

The Contractor shall complete CRACK FILL on a street a minimum Three (3) Weeks prior to applying slurry seal finish. The Contractor shall not proceed with application of the slurry seal until the Engineer has approved the surface preparation.

302-15.2 Materials.

302-15.2.1 Polymer Modified Emulsified Asphalt (PME). PME shall be grade PMCQS-1h conforming to 203-3.4.5 of the Greenbook ***except the polymer content shall be a minimum of 3.0 percent by weight of residual asphalt***.

302-15.2.2 Reclaimed Asphalt Pavement (RAP) Slurry Seal Aggregate.

302-15.2.2.1 General. RAP used to produce RAP slurry seal aggregate shall conform to 203-7.2.2, except for sand equivalent, and the requirements shown in Table 302-15.2.2.1.

TABLE 302-15.2.2.1

Tests	Test Method	Requirements
Percentage Wear, 500 Revolutions [1]	ASTM C131	35% Maximum
Sand Equivalent	ASTM D2419	60 Minimum
Soundness (5 Cycles) [1]	ASTM C88	15% Maximum
Durability	CTM 229	55 Minimum

Notes:

1. On RAP retained on No. 4 sieve.

302-15.2.2.2 Grading. The grading of the combined RAP aggregates shall conform to the requirements shown in Table 302-15.2.2.2.

TABLE 302-15.2.2.2

Requirements	Un-Extracted RAP Aggregate	Extracted RAP Aggregate (ASTM D1856)
	% of Combined Aggregate Passing Sieves (ASTM C136)	% of Combined Aggregate Passing Sieves (ASTM C136)
3/8” (9.5 mm)	100	
No. 4 (4.74 mm)	90 - 100	100
No. 8 (2.36 mm)	60 - 90	90 - 100
No. 16 (1.18 mm)	35 - 60	65 - 90
No. 30 (600 µm)	23 - 45	40 - 60
No. 50 (300 µm)	12 - 30	25 - 42
No. 100 (150 µm)	5 - 20	15 - 30
No. 200 (75 µm)	0.5 -10	10 – 20
Residual Asphalt Content (ASTM D6307), %		6.0 – 8.5

302-15.2.2.3 Water. Water shall conform to 203-3.2 of the Greenbook.

302-15.2.2.4 Set Control Agents. Set control agents shall conform to 203-5.4.2.5 of the Greenbook.